

OPERATOR: K.P. Kauffman Company Inc.
WELL: J.E. KIRKMEYER #1
FIELD: SPINDLE
API # 05-123-09974
LEASE #:
UIC #:

CNTY: WELD FTG:
STATE: CO Q-Q: NENW
SPUD: 6/20/1980 SEC.: 30
COMP: 8/7/1980 TWS: 1N
STATUS: PR RGE: 67W
WBD DATE: 8/9/2022 BY:

CURRENT WELLBORE DIAGRAM

KBE: 5119 '
KB: 10 '
GLE: 5109 '

TD (ft): 5070 '
PBDT (ft): 5006 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>225</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>5070</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4848</u>	<u>4926</u>	<u>158</u>		

12.25" Hole
8.625" 24# Csg @225
Cmtd w/200 sxs

DV Set @ 905'
Pump 2000 gal Angel

TOC @ 4060
Calc Assuming 1.15 yeild

7.875" Hole
4.5" 10.5# Csg @5070
Cmtd w/200 sxs

SUSSEX Perfs
4848'-4926'

PBDT (ft): 5006 '
TD (ft): 5070 '