


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADOSUNDRY NOTICES AND REPORTS ON WELLS
OIL & GAS CONSERVATION COMMISSION

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplete or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete ☐Report of Remedial Work ☒Notice of Intention to Change Plans ☐Report of Recompletion ☐Notice of Intention to Abandon Well ☐Other ☐

(Check appropriate space)

LEASE NAME Mosbarger WELL NO. 1FIELD Busy Bee WILDCAT COUNTY AdamsLOCATION C NW¹/₄ SW¹/₄ Section 10 Township 3S Range 60W Meridian 6th
(Quarter Quarter)
1980 feet from South Section Line and 660 feet from West Section Line
N or S E or W

(DETAILS OF WORK)

On 4/2/59 the "D" sand (perf. 6418-23') was acidized with three 250 gallon stages of Halliburton MCA - 7 $\frac{1}{2}$ % mud acid. On 4/3/59 the pay was treated with 15,330 gallons of gelled lease crude oil carrying 14,000 lbs. of 20/40 sand and 1000 lbs. of 10/20 sand at a final and maximum pressure of 3970 psig at an average injection rate of 17.7 bbls/min down the 4 $\frac{1}{2}$ " casing. After fishing for and recovering a casing swab for 11 days the well was put back on production in the original status. Production before treatment was 25 BOPD. Production after treatment is 55 BOPD. Well was restored to production 4/22/59.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	<input checked="" type="checkbox"/>
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

MAY - 8 1959

Date
Director A. J. JersinCompany Sunshine Mining Company Date 5/4/59Address 920 Patterson Bldg. Phone No. AC 2-0681By Title Dist. Geologist
(Signature)