

OPERATOR: K.P. Kauffman Company Inc.

WELL: JOSEPHINE B MILES 'B' #1

FIELD: SPINDLE

API # 05-123-09992

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 7/12/1980

COMP: 11/7/1980

STATUS: PR

WBD DATE: 8/10/2022

FTG:

Q-Q: SWSW

SEC.: 28

TWS: 2N

RGE: 68W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 4964 '

KB: 10 '

GLE: 4954 '

TD (ft): 5035 '

PBTD (ft): 4977 '

12.25" Hole
8.625" 24# Csg @246 '
Cmtd w/200 sxs

DV tool @ 650'
(Cmt Vol not rpt'd)

TOC @ 3016 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @5035 '
Cmtd w/400 sxs

SUSSEX Perfs
4444'-4490'

SHANNON Perfs
4888'-4914'

PBTD (ft): 4977 '

TD (ft): 5035 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>246</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>5035</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4444</u>	<u>4490</u>	<u>94</u>		
<u>SHANNON</u>	<u>4888</u>	<u>4914</u>	<u>54</u>		