

OPERATOR: K.P. Kauffman Company Inc.
WELL: LAWRENCE TOTEMS #2
FIELD: SPINDLE
API # 05-123-08485
LEASE #:
UIC #:

CNTY: WELD FTG:
STATE: CO Q-Q: SWSE
SPUD: 11/29/1975 SEC.: 24
COMP: 2/17/1976 TWS: 1N
STATUS: SI RGE: 68W
WBD DATE: 8/10/2022 BY:

CURRENT WELLBORE DIAGRAM

KBE: 5137 '
KB: 8 '
GLE: 5129 '

TD (ft): 4995 '
PBSD (ft): 4960 '

12.25" Hole
8.625" 24# Csg @773 '
Cmtd w/500 sxs

TOC @ 3985 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @4995 '
Cmtd w/200 sxs

SUSSEX Perfs
4846'-4876'

PBSD (ft): 4960 '
TD (ft): 4995 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
12 1/4	8 5/8	24		0	773
7 7/8	4 1/2	10.5		0	4995

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
SUSSEX	4846	4876	62		