

FORM
5A

Rev
09/20

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



| | | | |
|----|----|----|----|
| DE | ET | OE | ES |
|----|----|----|----|

Document Number:
402784008

Date Received:
11/15/2021

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

| | |
|---|--|
| 1. OGCC Operator Number: <u>10071</u> | 4. Contact Name: <u>Kate Miller</u> |
| 2. Name of Operator: <u>HIGHPOINT OPERATING CORPORATION</u> | Phone: <u>(720) 440-6116</u> |
| 3. Address: <u>555 17TH ST STE 3700</u> | Fax: _____ |
| City: <u>DENVER</u> State: <u>CO</u> Zip: <u>80202</u> | Email: <u>regulatory@civiresources.com</u> |

| | |
|--|-----------------------------------|
| 5. API Number <u>05-123-48183-00</u> | 6. County: <u>WELD</u> |
| 7. Well Name: <u>Anschutz Equus Farms Fed</u> | Well Number: <u>5-61-34-5649B</u> |
| 8. Location: QtrQtr: <u>NESE</u> Section: <u>34</u> Township: <u>5N</u> Range: <u>61W</u> Meridian: <u>6</u> | |
| 9. Field Name: <u>WATTENBERG</u> Field Code: <u>90750</u> | |

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: HYDRAULIC FRACTURING

Treatment Date: 07/07/2021 End Date: 07/28/2021 Date this Formation was Completed: 10/15/2021

Perforations Top: 6396 Bottom: 15850 No. Holes: 1560 Hole size: 0.25 Open Hole:

Describe the Formation Treatment, including the following: type of fluid used (gel, slickwater, etc.), type and concentration of acid used (HCl, HF, etc.), types and amounts of proppant(s) used, depth details of multiple zones, and method used to determine flowback volume.

52 stage wet shoe plug and perf: 621 bbls 15% HCl, 573,340 bbls slickwater, 9,905,350 lbs of 40/70 mesh, 6,820,610 lbs of 100 mesh, and 166,800 lbs of regional 100 mesh.

This formation is commingled with another formation: Yes No

Total fluid used in treatment (bbl): 573961 Max pressure during treatment (psi): 7445

Total gas used in treatment (mcf): 0 Fluid density at initial fracture (lbs/gal): 8.34

Type of gas used in treatment: _____ Min frac gradient (psi/ft): 0.92

Total acid used in treatment (bbl): 621 Number of staged intervals: 52

Recycled or Reused Fluids used in treatment (bbl): 0 Flowback volume recovered (bbl): 7153

Fresh water used in treatment (bbl): 573340 Disposition method for flowback: DISPOSAL

Total proppant used (lbs): 16892760

Fracture stimulations must be reported on FracFocus.org

Test Information:

10/29/2021 Hours: 24 Bbl oil: 249 Mcf Gas: 58 Bbl H2O: 715
Date Calculated 24 hour rate: Bbl oil: 249 Mcf Gas: 58 Bbl H2O: 715 GOR: 233
Test Method: Flowing Casing PSI: 915 Tubing PSI: 1034 Choke Size: 12/64
Gas Disposition: SOLD Gas Type: WET Btu Gas: 1346 API Gravity Oil: 38
Tubing Size: 2 + 3/8 Tubing Setting Depth: 5946 Tbg setting date: 09/29/2021 Packer Depth: 5936

Reason for Non-Production: _____

Date formation Abandoned: _____ Squeeze: Yes No If yes, number of sacks cmt _____

** Bridge Plug Depth: _____ ** Sacks cement on top: _____ ** Wireline and Cement Job Summary must be attached.

Comment:

Actual TPZ location: 1079' FSL and 579' FEL in Sec 34.
The bottom of the completed interval is at 1055' FSL and 515' FWL of Section 33.
The wellbore beyond the unit boundary setback is physically isolated by: wet shoe sub and float collar.
HighPoint Operating Corporation certifies that none of the wellbore beyond the unit boundary setback was completed.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Jenna Behm

Title: Regulatory Analyst Date: 11/15/2021 Email: regulatory@civiresources.com

Attachment List

Att Doc Num **Name**

| | |
|-----------|-------------------|
| 402784008 | FORM 5A SUBMITTED |
|-----------|-------------------|

Total Attach: 1 Files

General Comments

User Group

Comment

Comment Date

| |
|--|
| |
|--|

| |
|--|
| |
|--|

| |
|---------------------|
| Stamp Upon Approval |
|---------------------|

Total: 0 comment(s)