

OPERATOR: K.P. Kauffman Company Inc.

WELL: MLEYNEK, JACK A #4

FIELD: SPINDLE

API # 05-123-08964

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 10/1/1976

COMP: 12/5/1976

STATUS: PR

WBD DATE: 8/11/2022

FTG:

Q-Q: SESE

SEC.: 28

TWS: 2N

RGE: 68W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 5017 '

KB: 10 '

GLE: 5007 '

TD (ft): 5127 '

PBTD (ft): 5073 '

12.25" Hole
8.625" 24# Csg @495 '
Cmtd w/350 sxs

DV TOOL @ 608'
Cmtd w/ 150 sxs
TOC @ Surface
Calc Assuming 1.15 yield

TOC @ 3357 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @5124 '
Cmtd w/350 sxs

SUSSEX Perfs
4554'-4606'

SHANNON Perfs
4988'-5010'

PBTD (ft): 5073 '

TD (ft): 5127 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
12 1/4	8 5/8	24		0	495
7 7/8	4 1/2	10.5		0	5124

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
SUSSEX	4554	4606	106		
SHANNON	4988	5010	46		