

OPERATOR: K.P. Kauffman Company Inc.

WELL: PILAND #23-12

FIELD: GUIDON

API # 05-001-08145

LEASE #:

UIC #:

CNTY: ADAMS

STATE: CO

SPUD: 5/11/1982

COMP: 8/10/1982

STATUS: SI

WBD DATE: 8/11/2022

FTG:

Q-Q: NESW

SEC.: 12

TWS: 3S

RGE: 64W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 5445 '

KB: 10 '

GLE: 5435 '

TD (ft): 8023 '

PBTD (ft): 7915 '

12.5" Hole
9.625" 36# Csg @245 '
Cmt'd w/250 sxs

TOC @ 6993 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 11.6/10.5# Csg @8003 '
Cmt'd w/200 sxs

D SAND Perfs
7854'-7884'

J SAND Perfs
7932'-7950'

PBTD (ft): 7915 '

TD (ft): 8023 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/2</u>	<u>9 5/8</u>	<u>36</u>		<u>0</u>	<u>245</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>11.6/10.5</u>		<u>0</u>	<u>8003</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>D SAND</u>	<u>7854</u>	<u>7884</u>	<u>60</u>		
<u>J SAND</u>	<u>7932</u>	<u>7950</u>	<u>27</u>		