

OPERATOR: K.P. Kauffman Company Inc.  
WELL: ROCKY MOUNTAIN FUEL CO C #4  
FIELD: SPINDLE  
API # 05-123-07677  
LEASE #: \_\_\_\_\_  
UIC #: \_\_\_\_\_

CNTY: WELD  
STATE: CO  
SPUD: 5/7/1973  
COMP: 3/25/1973  
STATUS: PR  
WBD DATE: 8/11/2022

FTG: \_\_\_\_\_  
Q-Q: NESW  
SEC.: 9  
TWS: 1N  
RGE: 67W  
BY: \_\_\_\_\_

### CURRENT WELLBORE DIAGRAM

KBE: 5040 '  
KB: 10 '  
GLE: 5030 '

TD (ft): 4850 '  
PBDT (ft): 4802 '

12.25" Hole  
8.625" 23# Csg @219 '  
Cmtd w/200 sxs

TOC @ 2815 '  
Calc Assuming 1.15 yield

7.875" Hole  
4.5" 10.5# Csg @4834 '  
Cmtd w/400 sxs

SUSSEX Perfs  
4712'-4754'

PBDT (ft): 4802 '  
TD (ft): 4850 '

#### CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>23</u>		<u>0</u>	<u>219</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>4834</u>

#### TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

#### PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4712</u>	<u>4754</u>	<u>16</u>		