



00255678

OFFICE OF STATE OIL INSPECTOR
SUNDRY NOTICES AND REPORTS OF WELLS
LOCATED ON PRIVATE LANDS

138

(Indicate nature of data by checking below)

Notice of intention to drill.....
Notice of intention to change plans.....
Notice of date for test of water shut-off.....
Report on result of test of water shut-off.....
Notice of intention to re-drill or repair well.....
Notice of intention to clean out well.....
Statement of shooting.....
Statement of perforating and completing ☒.....
Notice to pull or otherwise alter casing.....
Notice of intention to abandon well.....
Report of work done on well since previous report.....

Following is a (~~notice of intention to do work~~) (On land) January 18, 1951
(report of work done) (patented) described as follows:

Colorado Logan Mt. Hope
State County Field
1 C. F. Green 25 NE 9N 54W 6 P.M.
(Well No.) (Lease) (Sec. and $\frac{1}{4}$ Sec.) (Twp.) (Range) (Meridian)
The well is located 330 ft. (X) of N Line and 330 ft. (X) of
E Line Sec. 25 (S) (W)

The elevation above sea level is 4216 ft. K.B. and 4206 ft. gd.

Details of Plan of Work: (State names of and expected depths to objective sands:
Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-
ing points, and all other important proposed work.)

After drilling firm cement from 4850 to 4917 with 7" casing cemented at 4930 perforations were placed in the casing opposite the oil bearing sand. On January 12, 1951, Lane-Wells shot 108 holes evenly spaced, 2 inches apart from 4888 to 4906 with 15/32" steel bullets. Swabbing then began through tubing. After 85 barrels of oil was swabbed from the hole, the well began flowing. From 12:30 P.M. January 14, 1951, to 9:45 P.M. January 14, 1951, the well flowed 343 barrels of clean oil. During the last 6 hour period, the rate of flow was 44 barrels per hour open flow for a calculated IP of 1056 barrels per day.

Approved: Jan 26 1951
John F. B...
State Oil Inspector

Company The Texas Company

Address Box 1346, Casper, Wyoming

By Walter Rand

Title District Superintendent

Submit reports of proposed work, for approval, on this form in Duplicate.