



OFFICE OF STATE OIL INSPECTOR  
SUNDRY NOTICES AND REPORTS OF WELLS  
LOCATED ON PRIVATE LANDS

3 approved copies  
Turned 5-10-51  
LB

138 B

(Indicate nature of data by checking below)

Notice of intention to drill.....  
Notice of intention to change plans.....  
Notice of date for test of water shut-off.....  
Report on result of test of water shut-off.....  
Notice of intention to re-drill or repair well.....  
Notice of intention to clean out well.....  
Statement of shooting.....  
Statement of perforating.....  
Notice to pull or otherwise alter casing.....  
Notice of intention to abandon well.....  
Report of work done on well since previous report setting production casing X.....

Following is a (~~notice of intention to do work~~) (On land) April 25, 1951  
(report of work done) (patented) described as follows:

Colorado Logan Mount Hope  
State County Field  
3 C. F. Green 25 NE 9N 54W 6 PM  
(Well No.) (Lease) (Sec. and  $\frac{1}{4}$  Sec.) (Twp.) (Range) (Meridian)  
The well is located 1695 ft. (~~N~~) of N Line and 330 ft. (~~E~~) of E Line  
(S) (W)

The elevation above sea level is 4213.3 ft. K.B. and 4203.85' ground.

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

On April 18, and 19, 1951, 7" casing was run and cemented at 4920' from Kelly Bushings with 150 sacks regular cement, 2% gel. mixture. The total depth of the hole being 5018' from Kelly Bushings. The description of the production casing is as follows: 23 jts., 23#, J-55, 8R thread, 728.02' on bottom, then 115 jts., 20#, J-55, 8R thread, 4154.20' landed with 1 jt., 32.88 ft. 23#, J-55, 8R thread. There were 2 centralizers placed at 4917' and 4879' with wall scratchers from 4915' to 4881'. A temperature survey to find the cement top in the annulus was not run. The cement was allowed to set 52 hours at which time the cement was drilled to 4915. Pump pressure of 750 psi. was applied with no indication of leaks so work was continued.

Approved: May 10, 1951  
John E. Brown  
State Oil Inspector

Company The Texas Company  
Address Box 1346, Casper, Wyoming  
By Walter Leland  
Title District Superintendent

Submit reports of proposed work, for approval, on this form in Duplicate.

CGCC (1)  
TTF (1)  
EWO (1) WR (1)