



OFFICE OF STATE OIL INSPECTOR
SUNDRY NOTICES AND REPORTS OF WELLS
LOCATED ON PRIVATE LANDS

3 approved copies
returned 5-10-51
JB

138 B

(Indicate nature of data by checking below)

Notice of intention to drill.....
Notice of intention to change plans.....
Notice of date for test of water shut-off.....
Report on result of test of water shut-off.....
Notice of intention to re-drill or repair well.....
Notice of intention to clean out well.....
Statement of shooting.....
Statement of perforating and completing X.....
Notice to pull or otherwise alter casing.....
Notice of intention to abandon well.....
Report of work done on well since previous report.....

Following is a (notice on intention to do work) (On land) April 27, 1951
(report of work done) (patented) described as follows:

Colorado Logan Mount Hope
State County Field
3 C. F. Green 25 NE 9N 54W 6 PM
(Well No.) (Lease) (Sec. and $\frac{1}{4}$ Sec.) (Twp.) (Range) (Meridian)

The well is located 1695 ft. ~~XX~~ of N Line and 330 ft. ~~XX~~ of
E Line (S) (W)

The elevation above sea level is 4213.3 ft. K.B. and 4203.85' ground

Details of Plan of Work: (State names of and expected depths to objective sands:
Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-
ing points, and all other important proposed work.)

After drilling firm cement from 4846' to 4915' with 7" casing cemented at 4920, perforations were placed in the casing opposite the oil bearing sand. On April 22 and 23, 1951, Lane-Wells shot 48 holes evenly spaced from 4883 to 4891 with 15/32" steel bullets. Swabbing then began through tubing. After 72 barrels oil was swabbed from the tubing, the well began to flow. From 5:30 PM, April 24, 1951, to 8:00 AM April 25, 1951, the well flowed 580 barrels clean oil for a calculated open flow IP of 960 barrels per day.

Approved: May 10 1951
John R. Brown
State Oil Inspector

Company The Texas Company
Address Box 1346, Casper, Wyoming
By Watts Rand
Title District Superintendent

Submit reports of proposed work, for approval, on this form in Duplicate.

EWO-YDE 5-4-51

CGCC (1) - TTF (1) - WR (1)