




OIL AND GAS CONSERVATION COMMISSION OF THE STATE OF COLORADO



OIL & GAS
CONSERVATION COMMISSION

PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Edward Mike Davis/dba/The Tiger Oil Company Field Wildcat Wildcat
Lease Name Colorado State Well No. 1 County Logan
Location C NE SW Section 36 Township 12N Range 54W Meridian 6th PM
(Quarter Quarter)
1980 feet from N Section line and 1935 feet from W Section Line
N or S E or W

TOTAL DEPTH 5713

DATE OF PLUGGING 11-7-1959

NO PRIOR
Approval

DETAILS OF WORK

The hole was filled with 10.5# mud to 225 feet. A 45 foot cement plug made up of 15 sacks of regular cement was set in and out of the base of the surface casing. The hole was then filled to within 30 feet of the surface. A 30 foot cement plug made up of 10 sacks of regular cement was set. A 2½" x 4 foot steel pipe was set in the top of the surface casing.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date NOV 17 1959

Director

Company The Tiger Oil Company Date 11-16-59

Address 1810 F. N. Bank Bldg. Phone No. Ch.4-8560

By Edward Mike Davis Title Owner
(Signature)

REMARKS-