



461960

Rig # 807-Milliken

### Cement Ticket

<b>Customer Name</b>	<b>Date Of Service:</b>
Chevron	8/11/2022

<b>Location</b>	<b>County</b>	<b>AFE</b>	<b>Equipment</b>
McCellan 03-32	Weld County, CO		C1003

#### Billing

Description	Qty	Rate	Total
P and A Charge(Each)			
Mileage(Miles)			
G Cement(Bags)			
Data Acquisition(Each)			
Iron Inspection(Each)			
Sugar(Lbs)			
Water Delivery(Barrels)			

Description	Qty	Rate	Total
Miscellaneous			
Miscellaneous			
Miscellaneous			
Miscellaneous			

defoamer  
retarder  
Turnkey  
rigless  
abandonmen  
t charge  
Wireline  
credit for  
tubing  
already at  
depth

<b>Description of Work</b>	<b>Start Time</b> 12:00 pm	<b>Stop Time</b> 08:30 pm
----------------------------	----------------------------	---------------------------

UWRWE-A2696-ABN Patricia Albidrez Gate to gate: 12:00 pm – 5:30 pm MOB to location, spot in, rig up, flowback incinerated gas, Status: 2-3/8" 4.7# tubing cut at 7,031' inside 4 -1/2" 11.6# casing, pump down tubing, pump 33 bbl. freshwater, pumped 1 bbl. LCM pill, displaced with 26.4 bbl. waited 30 minutes, established circulation with 60 bbl. of water, pumped 115 bbl. total water, pumped 5 bbl. freshwater spacer, mix and pumped 32 sxs of 15.8# 1.15 cu.ft./sack Class G cement with retarder, 6.5 bbl. of slurry, displaced with 26 bbl. to cover from 6,510' to 7,031', RD valve, wash out pump; 4:30 MOB to yard Non rev: post-trip truck, prep for job, load cement; fix shotgun valve on compressor and replace key stock on mule shoe

#### Payroll Section

Employee		Rev Hrs.	Travel Hrs.	Non Rev Hrs.	Total
Supervisor	Pena, Marcos	5.50	0.00	3.00	8.50
Operator	Meza, Abraham	5.50	0.00	2.50	8.00
Derrick	Soto, Juan I.	5.50	0.00	2.50	8.00

No UnReported Incidents Per My Signature

Ranger Tool Pusher

Customer/Agent: