

	33		
X			

Loca
Well
Correctly

00278706

AUG 18 1955

OIL & GAS
CONSERVATION COMMISSIONFile in triplicate. n Fee and Patented lands and in
quadruplicate on State and School lands, with

OFFICE OF DIRECTOR

OIL AND GAS CONSERVATION COMMISSION,
STATE OF COLORADO

LOG OF OIL AND GAS WELL

Field Cliff Company T. & T. Oil Co., 609 S Grand Ave.
County Logan Address Los Angeles, California
Lease UPRR-Casement
Well No. 2 Sec. 33 Twp. 12N Rge. 54W Meridian 6 State or Pat. Pat
Location 660 Ft. ^(N)33 of South Line and 660 Ft. ^(E)33 of West line of 33 Elevation 4437
(Derrick floor relative to sea level)

The information given herewith is a complete and correct record of the well and all work done thereon so far as can be determined from all available records.

Signed E.W. OlsonDate August 15, 1955Title Agent

The summary on this page is for the condition of the well as above date.

Commenced drilling July 4, 1955 Finished drilling July 24, 1955

OIL AND GAS SANDS OR ZONES

No. 1, from 5367 to 5409 No. 4, from _____ to _____
No. 2, from 5521 to 5525 No. 5, from _____ to _____
No. 3, from _____ to _____ No. 6, from _____ to _____

IMPORTANT WATER SANDS

No. 1, from 5525 to 5556 No. 3, from _____ to _____
No. 2, from _____ to _____ No. 4, from _____ to _____

CASING RECORD

SIZE	WT. PER FOOT	MAKE	WHERE LANDED	NO. OF SKS. CEMENT	STOOD HOURS	PRESSURE TEST PSI
9-5/8			200	150	40	500
5-1/2	15.5	Spang	5572	175	72	1000

COMPLETION DATA

Total Depth 5576 ft. Cable Tools from _____ to _____ Rotary Tools from 0 to 5576
Casing Perforations (prod. depth) from 5406 to 5409 ft. No. of holes 18
Acidized with _____ gallons. Other physical or chemical treatment of well to induce flow _____
Shooting Record _____

Prod. began August 2, 1955. Making 186 bbls./day of 40 A. P. I. Gravity Fluid on _____ Pump ☒
Tub. Pres. 50 lbs./sq. in. Csg. Pres. 425 lbs./sq. in. Gas Vol. _____ Mcf. Gas Oil Ratio _____
Length Stroke 54 in. Strokes per Min. 12 Diam. Pump 1-3/4 in.
B. S. & W. _____ % Gas Gravity _____ BTU's/Mcf. _____ Gals. Gasoline/Mcf. _____

WELL DATA

Indicate (yes or no) whether or not the following information was obtained.

Electrical Log yes Date July 24, 1955Straight Hole Survey yes Type Totco

Date _____, 19____

Other Types of Hole Survey _____ Type _____

Time Drilling Record yes

(Note—Any additional data can be shown on reverse side.)

Core Analysis NO Depth _____ to _____

FORMATION RECORD

Show all formations, especially all sands and character and contents thereof.

FORMATION	TOP	BOTTOM	REMARKS
Shale	0	5367	Shale rotten with lime streaks
"D" Sand	5367	5409	Gas & Oil Sand with shale streaks
Shale	5409	5481	Shale
"J" Sand	5481	5569	Sand with oil & gas show in center 4 feet.

(Continue on reverse side)

Produce

AJJ	
DVR	
FJK	
OPS	
HHM	
AH	
JJD	
FILE	