



**Cement Ticket**

<b>Customer Name</b> Chevron	<b>Date Of Service:</b> 8/23/2022
---------------------------------	--------------------------------------

<b>Location</b> OCOMA C31-23	<b>County</b> Weld County, CO	<b>AFE</b>	<b>Equipment</b> C1003
---------------------------------	----------------------------------	------------	---------------------------

Billing			
Description	Qty	Rate	Total
P and A Charge(Each)			
Mileage(Miles)			
G Cement(Bags)			
Data Acquisition(Each)			
Iron Inspection(Each)			
Sugar(Lbs)			
Water Delivery(Barrels)			

  

Description	Qty	Rate	Total	
Miscellaneous				defoamer
Miscellaneous				retarder
Miscellaneous				Turnkey rigless abandonmen t charge
Miscellaneous				water bobtail hours
Miscellaneous				wireline gauge ring charge

<b>Description of Work</b>	<b>Start Time</b> 06:00 am	<b>Stop Time</b> 06:00 pm
----------------------------	----------------------------	---------------------------

UWRWE- A2329 -ABN Patricia Albidrez Gate to gate: 6:30 am – 4:00 pm MOB to location, spot in, rig up, waited on flowback to incinerate gas,3:45 PM Status: 2-3/8" 4.7# tubing cut at 6,793' inside 4-1/2" 11.6# casing , pumped 32 bbl of freshwater, pumped 3 bbl. LCM pill, displaced with 25.4 bbl. waited 30 minutes, established circulation with 61 bbl. of water, pumped 115 bbl. total water, pumped 5 bbl. freshwater spacer, mix and pumped 35 sxs of 15.8# 1.15 cu.ft./sack Class G cement with retarder, 7.2 bbl. of slurry, displaced with 25 bbl. to cover from 6,793' to 6,280', RD valve, wash out pump; 1:00 PM MOB to next well. Spot in, Rig up; job pushed till next day, due to high pressure. 3:00 PM MOB to yard. Non rev: post-trip truck, prep for job; repair love-joy on driver side water pump.

Payroll Section					
Employee	Rev Hrs.	Travel Hrs.	Non Rev Hrs.	Total	
Supervisor Pena, Marcos	9.50	0.00	2.00	11.50	
Operator Soto, Juan I.	5.00	0.00	0.50	5.50	

No UnReported Incidents Per My Signature

\_\_\_\_\_  
 Ranger Tool Pusher

\_\_\_\_\_  
 Customer/Agent: