

RECEIVED
OCT4- 1963
OIL & GAS
CONSERVATION COMMISSION



AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplete or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete	<input type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of <u>Recompletion</u>	<input checked="" type="checkbox"/>
Notice of Intention to Abandon Well	<input type="checkbox"/>	Other	<input type="checkbox"/>

(Check appropriate space)

LEASE NAME Casement WELL NO. A-3

FIELD Cliff WILDCAT COUNTY Logan

LOCATION SW, SE, Section 32 Township 12 N Range 54 W Meridian 6 PM

660 feet from south Section Line and 1987 feet from East Section Line

N or S E or W

(DETAILS OF WORK)

Ran Packer, on Tubing, and set at 5390'KB. Cement squeezed "D" sand perforations at 5414-5428 with 77 sax regular with 0.8% Halad 9 water loss additive at 500 to 1500 PSI. Drilled out hard cement and the CIBP at 5430 and found tight spot in casing from 5415 to 5432. Used smaller bit and drilled and clean out to 5540. Water started entering hole the last 10 feet drilled. Squeezed 200 sax to formation at maximum pressure of 3500 PSI. Drilled out cement from 5332 to 5432 and tools stuck. In attempt to loosen, lost tools in hole and could not recover. Casing has been capped and well is temporarily abandoned.

DVR	
WRS	
HHM	
JAM	
FJP	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

OCT 7 1963

Date

Director *M. Rogers*

Company British-American Oil Co Date Oct. 3, 1963

Address Box 180; Denver 1, Colo. Phone No. 222 9401

By *Thomas H. Stipan* Title Dist. Supt.

(Signature)