



# AND GAS CONSERVATION COMMISSION OF THE STATE OF COLORADO

RECEIVED  
APR 29 1964

OIL & GAS  
CONSERVATION COMMISSION

## PLUGGING RECORD

### INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator British-American Oil Producing Co. Field Cliff Wilcoat  
Lease Name Casement Well No. A-3 County Logan  
Location SW, SE, Section 32 Township 12 N Range 54 W Meridian 6PM  
(Quarter Quarter)  
660 feet from South Section line and 1987 feet from East Section Line  
N or S E or W

TOTAL DEPTH 5624'KB

DATE OF PLUGGING 3-20-64

### DETAILS OF WORK

Set rock and cement bridge, above perforations, at 5302'KB. Shot casing off at 3645'GL and pulled, leaving 1969' of 5½" casing in hole from 3655'KB to 5624'KB. Filled hole with heavy mud with a 15 sax cement plug across bottom of surface casing and a 10 sax cement plug in top of surface casing, welded a steel plate on top of surface casing, cleaned up and levelled location. There was 202' of 9-5/8" surface casing left in hole.

*Location checked on 8/4/64,  
Hole P & A - OK, Jim*

*EX  
Oil  
Prod.*

DVR	
WRS	
HHM	
JAM	✓
FJP	✓
JJD	✓
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date MAY 1 1964

D. V. Rogers  
Director

Company British-American Oil Date 4-28-64

Address Box 180; Denver, Colo. Phone No. 222 9401

By James H. Stone Title Dist. Engineer  
(Signature)