

RECEIVED

FEB 14 1967

COLO. OIL & GAS CONS. COMM.

**OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO**

SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recompleat or abandon a well or to change plans. Within thirty (30) days after recompleat, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

<input checked="" type="checkbox"/> Notice of Intention to Recomplete	<input checked="" type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Recompletion	<input type="checkbox"/>
Notice of Intention to Abandon Well	<input type="checkbox"/>	Other	<input type="checkbox"/>

(Check appropriate space)

LEASE NAME Casement A WELL NO. 5

FIELD Cliff WILDCAT COUNTY Logan

LOCATION C SE SE Section 32 Township 12N Range 54W Meridian 6 PM
(Quarter Quarter)

 feet from Section Line and feet from Section Line
N or S E or W

(DETAILS OF WORK)

Elevation: 4458' KB; 4448' Gnd; Surface Pipe: 9-5/8" at 213' with 160 sacks.
Casing: 5-1/2" with 150 sacks. TD 5620', PBTD 5582'. Perforations 5400' - 5410'
and 5424' - 5430' with 45 PF.

This well is presently producing from the "D" Sand and the last test was 7 BOPD - 30 BWPD. This zone is fast approaching the economic limit.

We propose to run a retrievable bridge plug and set above the present perforations and then perforate the Niobrara Shale zones 4593' - 4600' and 4714' - 4718'. A small clean up acid job is planned before swab testing these zones.

DVR	
FJP	/
HHM	
JAM	.
JJD	✓

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

FEB 16 1967

Date _____
Director W. Rogers

Company Gulf Oil Corporation Date 2-13-67

P. O. Box 1971

Address Casper, Wyoming Phone No 235-5783

By Lester LeFavour Title Area Prod. Mgr.
(Signature) Lester LeFavour

(Signature)

Lester LeFavour