



OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

RECEIVED
APR -3 1964

OIL & GAS
CONSERVATION COMMISSION

SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recompleate or abandon a well or to change plans. Within thirty (30) days after recompleation, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

<input checked="" type="checkbox"/> Notice of Intention to Recomplete	<input checked="" type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Recompleation	<input type="checkbox"/>
Notice of Intention to Abandon Well	<input type="checkbox"/>	Other	<input type="checkbox"/>

(Check appropriate space)

LEASE NAME CASEMENT WELL NO. A-1
 FIELD Cliff WILDCAT COUNTY Logan
 LOCATION NW, SE, Section 32 Township 12 N Range 54 W Meridian 6PM
 (Quarter Quarter)
1880 feet from South Section Line and 1863 feet from East Section Line
 N or S E or W

(DETAILS OF WORK)

This well completed in May 1955 as a "D" sand oil well and has a cumulative of 184,789 barrels oil. On last AVT 12-29-63 the production was no oil and 78 barrels water in 24 hours and has been shut in since that time.

It is proposed to cement squeeze the "D" sand at perforated intervals 5447-52, 5457-60 and 5470-80, perforate the "J" sand interval 5562-66, top of which is at 5555 per Schlumberger, clean out and swab test for conclusive production. The estimated recovery from "J" sand is 5600 barrels oil. Your permission is requested.

DVR	
WRS	
HHM	
JAM	
FJP	
JJD	<input checked="" type="checkbox"/>
FILE	

ORDER 66-1 { O & J Sds 40 ac. well - C & 40's 76L = 150 ft.
5-12-55 for instructions

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

APR 3 1964
 Date
 Director W. Rogers

Company British-American Oil Co Date April 2, 1964

Address Box 180; Denver, Colo. Phone No. 222 9401

By James M. Rogers Title Dist Supt
 (Signature)