

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

PLUGGING RECORD

RECEIVED
NOV 9 - 1964
OIL & GAS
CONSERVATION COMMISSION

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator The British-American Oil Producing Company Field Cliff ~~WIDEOK~~
Lease Name Casement Well No. A-1 County Logan
Location ~~NW~~ SE Section 32 Township 12N Range 54W Meridian 6 P.M.
(Quarter Quarter)
1880 feet from S Section line and 1863 feet from E Section Line
Nor S E or W

TOTAL DEPTH 5658' KBDATE OF PLUGGING 10-23-64

DETAILS OF WORK

Dumped sand 5658' to 5630' KB. Dumped 10 sax cement 5630' to 5550' KB. Shot 5-1/2" casing off at 4485' KB. Pulled and laid down 140 joints casing. Filled hole with heavy mud 5550' to 230' KB. Dumped 10 sax cement in bottom of surface casing 230' to 198'. Filled with mud to 18'; ran 5 sax cement from 18' to base of cellar. Filled cellar with earth, rock and top soil. Well is plugged and abandoned.
FINAL REPORT.

EX
Oil
Prod

DVR	
WRS	
HHM	
JAM	
FJP	✓
JJD	✓
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date NOV 10 1964

Director

The British-American
Company Oil Producing Company Date 11-6-64
P. O. Box 180
Address Denver, Colorado Phone No. 222-9401
By Thomas M. Hogan Title Dist. Supt.
(Signature)



05-076-07208