




COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



OIL & GAS
CONSERVATION COMMISSION

(Indicate nature of data by checking below)

Notice of intention to drill (attach plat) _____
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing ☒
 Notice of intention to abandon well ☒
 Report of work done on well since previous report _____

Locate Well Correctly

	36		

Notice to do work ☒
 Report of work done ☐

Land: Fee and Patented ☐
 State ☒

Lease No. 3831

COLORADO

LOCAN

NW GRAYLIN

State

County

Field

2

STATE "B"

SE

36

9N

54W

6th P.M.

(Well No.)

(Lease)

(1/4 Sec.)

(Sec.)

(Twp.)

(Range)

(Meridian)

The Well is located 330 Ft. (N) of Section Line and 1650 Ft. (E) of
 Section Line. or SE SW SE (S) (W)

The elevation above sea level is 4244 Ft.

Details of Plan of Work: (State names of and expected depths to objective sands.
 Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing
 points, and all other important proposed work.)

TD 5171' PBD 5121' 10 3/4" casing was set at 253' with 200 sacks cement, 5 1/2" casing
 was set at 5171' with 300 sacks cement. Present perforations in "J" sand 5068 to 5075'.
 "D" sand was adequately tested on completion and had no commercial oil or gas
 production. Well has produced 18,480 barrels oil and 6,173 barrels water. Well was
 shut in July 18, 1955 due to producing all water and no oil. Propose to place 5 sacks
 cement over perforations 5068 to 5075'. Shoot off 5 1/2" casing at approximately
 3800' and pull same. Fill hole with mud. Lay 10 sack cement plug in bottom of
 surface casing, 10 sacks in top of surface casing. Weld metal cap in top of surface
 casing and erect marker. Well will be plugged and abandon.

AJJ	
DVR	
FJK	
WRS	
HHM	
AH	
JJD	
FILE	

Approved: JAN 10 1956

Date January 9, 1956

Company J. Ray McDermott & Co., Inc.

Address Drawer 352 Sterling, Colorado

By Paul Speck, Jr.

Title Dist. Clerk

Submit reports of proposed work, for approval, on this form in Duplicate for patented
 lands and in Triplicate for school and state lands.

Producers now P.A.