




# AND GAS CONSERVATION COMMISSION OF THE STATE OF COLORADO



OIL & GAS  
CONSERVATION COMMISSION

## PLUGGING RECORD

12360028

### INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Don M. Rounds Company 75230 Field \_\_\_\_\_ Wildcat ☒  
Lease Name Cervený Well No. 1 County Weld  
Location C. NW SE Section 19 Township 12N. Range 56W. Meridian 6th P.M.  
(Quarter Quarter)  
1980 feet from South Section line and 1980 feet from East Section Line  
N or S E or W

TOTAL DEPTH 6566 DATE OF PLUGGING April 29, 1960

under 4/28/60  
any

### DETAILS OF WORK

Filled hole with heavy mud from total depth at 6566' to base of surface pipe at 234'. A 15 sack cement plug was spotted with bottom at 240'. Remainder of surface pipe was filled with heavy mud. A 5 sack plug was placed in the top of surface casing. Surface casing was cut off below plow depth and a steel cap welded on top of surface casing.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	<input checked="" type="checkbox"/>
FILE	

Visited 6/6/60  
appears OK

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date May 10, 1960

Director

Company DON M. ROUNDS COMPANY Date May 9, 1960  
925 Petroleum Club Building,  
Address Denver 2, Colorado Phone No. MA 3-0296

By

(Signature)

Title Petroleum Engr.

