

FORM
2

Rev
05/22

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402988838

(SUBMITTED)

Date Received:

09/25/2022

APPLICATION FOR PERMIT TO

Drill Deepen Re-enter Recomplete and Operate

Amend

TYPE OF WELL OIL GAS COALBED OTHER: _____

Refile

ZONE TYPE SINGLE ZONE MULTIPLE ZONES COMMINGLE ZONES

Sidetrack

Well Name: FEDERAL Well Number: RG 314-18-297
 Name of Operator: TEP ROCKY MOUNTAIN LLC COGCC Operator Number: 96850
 Address: 1058 COUNTY ROAD 215
 City: PARACHUTE State: CO Zip: 81635
 Contact Name: Jeff Kirtland Phone: (970)263-2736 Fax: ()
 Email: jkirtland@terraep.com

FINANCIAL ASSURANCE FOR PLUGGING, ABANDONMENT, AND RECLAMATION

COGCC Financial Assurance

The Operator has provided or will provide Financial Assurance to the COGCC for this Well.

Surety ID Number (if applicable): _____

Federal Financial Assurance

In checking this box, the Operator certifies that it has provided or will provide at least this amount of Financial Assurance to the federal government for this Well. (Per Rule702.a.)

Amount of Federal Financial Assurance \$ _____

WELL LOCATION INFORMATION

Surface Location

QtrQtr: LOT 12 Sec: 13 Twp: 2S Rng: 98W Meridian: 6

Footage at Surface: 947 Feet FSL 1081 Feet FEL

Latitude: 39.871786 Longitude: -108.337965

GPS Data: GPS Quality Value: 1.5 Type of GPS Quality Value: PDOP Date of Measurement: 07/21/2021

Ground Elevation: 6667

Field Name: SULPHUR CREEK Field Number: 80090

Well Plan: is Directional Horizontal (highly deviated) Vertical

If Well plan is Directional or Horizontal attach Deviated Drilling Plan and Directional Data.

Subsurface Locations

Top of Productive Zone (TPZ)

Sec: 18 Twp: 2S Rng: 97W Footage at TPZ: 552 FSL 1020 FWL
Measured Depth of TPZ: 6749 True Vertical Depth of TPZ: 6467 FNL/FSL FEL/FWL

Base of Productive Zone (BPZ)

Sec: 18 Twp: 2S Rng: 97W Footage at BPZ: 552 FSL 1020 FWL
Measured Depth of BPZ: 12086 True Vertical Depth of BPZ: 11767 FNL/FSL FEL/FWL

Bottom Hole Location (BHL)

Sec: 18 Twp: 2S Rng: 97W Footage at BHL: 552 FSL 1020 FWL
FNL/FSL FEL/FWL

LOCAL GOVERNMENT PERMITTING INFORMATION

County: RIO BLANCO Municipality: N/A

Is the Surface Location of this Well in an area designated as one of State interest and subject to the requirements of § 24-65.1-108 C.R.S.? No

Per § 34-60-106(1)(f)(I)(A) C.R.S., the following questions pertain to the Relevant Local Government approval of the siting of the proposed Oil and Gas Location.

SB 19-181 provides that when "applying for a permit to drill," operators must include proof that they sought a local government siting permit and the disposition of that permit application, or that the local government does not have siting regulations. § 34-60-106(1)(f)(I)(A) C.R.S.

Does the Relevant Local Government regulate the siting of Oil and Gas Locations, with respect to this Location? [X] Yes [] No

[X] If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location.

The disposition of the application filed with the Relevant Local Government is: Approved Date of Final Disposition: 04/29/2022

Comments: Rio Blanco County Oil or Gas Well Pad Special Use/Building Permit: COGW-0002-22

SURFACE AND MINERAL OWNERSHIP AT WELL'S OIL & GAS LOCATION

Surface Owner of the land at this Well's Oil and Gas Location: [] Fee [] State [X] Federal [] Indian

Mineral Owner beneath this Well's Oil and Gas Location: [] Fee [] State [X] Federal [] Indian

Surface Owner Protection Bond (if applicable): Surety ID Number (if applicable):

MINERALS DEVELOPED BY WELL

The ownership of all the minerals that will be developed by this Well is (check all that apply):

- [] Fee
- [] State
- [X] Federal
- [] Indian
- [] N/A

LEASE INFORMATION

Using standard QtrQtr, Section, Township, Range format describe one entire mineral lease as follows:

* If this Well is within a unit, describe a lease that will be developed by the Well.

* If this Well is not subject to a unit, describe the lease that will be produced by the Well.

(Attach a Lease Map or Lease Description or Lease if necessary.)

T2S-R97W
 SEC 18: S2NE4, E2W2, SE4, LOTS 1-4
 T2S-R98W
 SEC 12: N2SW4, S2NW4, SW4NE4, NE4NW4, LOTS 17-20
 SEC 13: LOTS 1-12, SW4
 SEC 14: E2SE4, LOTS 1, 8
 SEC 23: E2NE4, N2SE4, SW4NE4
 SEC 24: N2, N2S2

Total Acres in Described Lease: 2371 Described Mineral Lease is: Fee State Federal Indian

Federal or State Lease # COC0003453

SAFETY SETBACK INFORMATION

Distance from Well to nearest:

Building: 5280 Feet
 Building Unit: 5280 Feet
 Public Road: 4831 Feet
 Above Ground Utility: 5114 Feet
 Railroad: 5280 Feet
 Property Line: 4960 Feet

INSTRUCTIONS:

- Specify all distances per Rule 308.b.(1).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit – as defined in 100 Series Rules.

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ILES	ILES	1-229		
WILLIAMS FORK	WMFK	1-229		

Federal or State Unit Name (if appl): _____

Unit Number: _____

SUBSURFACE MINERAL SETBACKS

Enter 5280 for distance greater than 1 mile.

Is this Well within a unit? No

If YES:

Enter the minimum distance from the Completed Zone of this Well to the Unit Boundary: _____ Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well within the same unit permitted or completed in the same formation: _____ Feet

If NO:

Enter the minimum distance from the Completed Zone of this Well to the Lease Line of the described lease: 552 Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well producing from the same lease and permitted or completed in the same formation: 349 Feet

Exception Location

If this Well requires the approval of a Rule 401.c Exception Location, enter the Rule or spacing order number and attach the Exception Location Request and Waivers. _____

SPACING & FORMATIONS COMMENTS

DRILLING PROGRAM

Proposed Total Measured Depth: 12086 Feet

TVD at Proposed Total Measured Depth 11767 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 249 Feet No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No If yes, attach an H₂S Drilling Plan unless a plan was already submitted with the Form 2A per Rule 304.c.(10).

Will there be hydraulic fracture treatment at a depth less than 2,000 feet in this well? No

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: Annular Preventor Double Ram Rotating Head None

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Grade	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	30	20	X-65	78.67	0	80	230	80	0
SURF	17+1/2	13+3/8	J-55	54.5	0	1354	442	1354	0
1ST	12+1/4	9+5/8	J-55	36	0	3087	154	3087	2087
2ND	8+3/4	4+1/2	P-110	11.6	0	12086	992	12086	6549

Conductor Casing is NOT planned

POTENTIAL FLOW AND CONFINING FORMATIONS

Zone Type	Formation /Hazard	Top M.D.	Top T.V.D.	Bottom M.D.	Bottom T.V.D.	TDS (mg/L)	Data Source	Comment
Groundwater	UINTA	30	30	885	880	501-1000	Produced Water Sample	
Groundwater	GRRV	885	880	1039	1030	501-1000	Produced Water Sample	
Subsurface Hazard	GRRV A GROOVE	1039	1030	1238	1220			
Subsurface Hazard	GRRV B GROOVE	1238	1220	1564	1530			
Subsurface Hazard	GRRV DISSOLUTION SURF	1564	1530	2288	2220			Potential Loss Zone
Confining Layer	GARDEN GULCH	2288	2220	2477	2400			
Confining Layer	GRRV ORANGE	2477	2400	2561	2480			
Confining Layer	U WASATCH	2561	2480	4788	4600			
Hydrocarbon	G SAND	4788	4600	5224	5015			Potential Loss Zone/Non-Productive Zone
Hydrocarbon	FT UNION	5224	5015	6048	5800			
Confining Layer	L WASATCH	6048	4800	6749	6467			
Hydrocarbon	OHIO CREEK	6749	6467	7500	7187			
Hydrocarbon	U MESAVERDE	7500	7187	8306	7987			
Hydrocarbon	KMVGAS	8306	7987	9876	9557			
Hydrocarbon	CAMEO	9876	9557	10606	10287			
Hydrocarbon	ROLLINS	10606	10287	10756	10437			
Hydrocarbon	COZZETTE	10756	10437	11081	10762			
Hydrocarbon	CORCORAN	11081	10762	11341	11022			
Hydrocarbon	UPPER SEGO	11341	11022	11586	11267			
Hydrocarbon	LOWER SEGO	11586	11267	12086	11767			

OPERATOR COMMENTS AND SUBMITTAL

Comments: Nearest permitted or completed well in same formation: Federal RG 414-18-297 (Doc #402988817).

The Federal OG Colo 03435 # 9 well (05-103-05161) was used for the distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator (AC Report).

OGDP Application (Docket #220500097) and Form 2A (Doc #402932454) approved on 09/21/2022.

This application is in a Comprehensive Area Plan No CAP #: _____

Oil and Gas Development Plan Name Ryan Gulch Phase 2 OGDP ID#: 482485

Location ID: 315513

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Melissa Luke

Title: Regulatory Specialist Date: 9/25/2022 Email: mluke@terraep.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-181 and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____
Expiration Date: _____

API NUMBER

05

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type **Description**

Best Management Practices

No BMP/COA Type **Description**

No BMP/COA Type	Description
1 Drilling/Completion Operations	Alternative Logging Program: One of the first wells drilled on this pad will be logged with an open-hole resistivity log with gamma-ray, from TD into the 9 5/8" casing shoe. All wells on the pad will have a cement bond log (CBL) with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs will state "Alternative Logging Program - No open-hole logs were run" and will clearly identify the type of log and the well (by API#) in which open-hole logs were run.

Total: 1 comment(s)

Attachment List

Att Doc Num **Name**

Att Doc Num	Name
403046744	WELL LOCATION PLAT
403048917	DIRECTIONAL DATA
403048918	DEVIATED DRILLING PLAN
403052686	OffsetWellEvaluations Data

Total Attach: 4 Files

General Comments

User Group **Comment**

Comment Date

User Group	Comment	Comment Date
		Stamp Upon Approval

Total: 0 comment(s)

Public Comments

No public comments were received on this application during the comment period.

