

OPERATOR: K.P. Kauffman Company Inc.

WELL: Anderson #1

FIELD: Wattenberg

API # 05-123-10558

LEASE #:

UIC #:

CNTY: Weld

STATE: CO

SPUD: 11/4/1981

COMP: 11/19/1982

STATUS: PR

WBD DATE: 9/22/2022

FTG:

Q-Q: NESW

SEC.: 32

TWS: 4N

RGE: 67W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 4964 '

KB: 10 '

GLE: 4954 '

TD (ft): 7410 '

PBTD (ft): 7332 '

12 1/4" Hole
8 5/8" 24# Csg @ 320 '
Cmtd w/ 200 sxs

TOC @ 6830 '

CBL

7 7/8" Hole
4 1/2" 11.6# Csg @ 7410 '
Cmtd w/ 225 sxs

Codell Perfs
7304'-7309'

PBTD (ft): 7332 '

TD (ft): 7410 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>320</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>11.6</u>		<u>0</u>	<u>7410</u>

TUBING RECORD

COND:

DATE:

SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	TALLY (ft)	JTS

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>Codell</u>	<u>7304</u>	<u>7304</u>	<u>11</u>		

WELLWORK HISTORY

Codell

182,500# 20/40 sand, 15,000# 20/40 bauxite, 1,905 BBLs gel