



RECEIVED

JUL 17 1967

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

COLO. OIL & GAS CONS. COMM.

SUNDRY NOTICES AND REPORTS ON WELLS

INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recomplate or abandon a well or to change plans. Within thirty (30) days after recompletion, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete	<input type="checkbox"/>	Report of Remedial Work	<input type="checkbox"/>
Notice of Intention to Change Plans	<input type="checkbox"/>	Report of Recompletion	<input type="checkbox"/>
Notice of Intention to Abandon Well	<input checked="" type="checkbox"/>	Other	<input type="checkbox"/>

(Check appropriate space)

LEASE NAME Kinzie WELL NO. 1

FIELD Tomahawk WILDCAT _____ COUNTY Logan

LOCATION NE-NE Section 10 Township 9N Range 55W Meridian 6th
(Quarter Quarter)

660 feet from North Section Line and 660 feet from East Section Line
N or S E or W

(DETAILS OF WORK)

Well shut down, non commercial. 4½" OD casing set @ 5639' KB and perf. from 5580'-5583 w/4 JSPF. 8-5/8" OD casing set @ 130' KB. Cemented to surface.
Plan to plug and abandon as follows:

1. Move in and rig up service unit;
2. Pull and lay down rods and tubing;
3. Fill casing with sand to 5570'KB, covering perforations @ 5580'-5583'KB;
4. Dump 5 sx. regular cement on top of sand from 5570'-5505'KB;
5. Cut off 4½" OD, 10.5#, J-55 production casing at approx. 5000' and salvage same;
6. Dump 15 sx. regular cement from 145'-100' KB covering 8-5/8" OD surface casing shoe set @ 130' KB;
7. Dump 5 sx. regular cement from 23' KB to surface;
8. Weld cap on surface casing;
9. Balance of hole filled w/heavy drilling mud and water;
10. Remove equipment, clean up location.

DVR	<input type="checkbox"/>
FJP	<input checked="" type="checkbox"/>
HMM	<input type="checkbox"/>
JAM	<input type="checkbox"/>
JJD	<input checked="" type="checkbox"/>

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:
JUL 19 1967
Date _____
Director [Signature]

Company DEPCO, INC. Date July 17, 1967
825 Petroleum Club Bldg.
Address Denver, Colorado 80202 Phone No. 292-0980
By [Signature] Title Dist. Prod. Supt.
(Signature)