

OFFICE OF STATE OIL INSPECTOR
SUNDRY NOTICES AND REPORTS OF WELLS
LOCATED ON PRIVATE LANDS



(Indicate nature of data by checking below)

Notice of intention to drill.....X
Notice of intention to change plans.....
Notice of date for test of water shut-off.....
Report on result of test of water shut-off.....
Notice of intention to re-drill or repair well.....
Notice of intention to clean out well.....
Statement of shooting.....
Statement of perforating.....
Notice to pull or otherwise alter casing.....
Notice of intention to abandon well.....
Report of work done on well since previous report.....

December 14, 1950
Following is a (notice on intention to do work) (On land)
(~~report of work done~~) (patented) described as follows:

State	County	Field
COLORADO	LOGAN	YENTER BLOCK
2	KOENIG ASHBY 2W-5E-4 SW 1/4 Sec. 34	9N 54 W 6th
(Well No.)	(Lease) (Sec. and 1/4 Sec.) (Twp.)	(Range) (Meridian)

The well is located 330 ft. (N) of S Line and 990 ft. (E) of E Line
(S) (W)
Sec. 34

The elevation above sea level is 4375 ft. G.L. Est.

Details of Plan of Work: (State names of and expected depths to objective sands:
Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-
ing points, and all other important proposed work.)

To drill with Rotary Tools and test subject well to the "J" sand of the Granerous
sand series expected at approximately 5216'.
Surface Casing to be 8-5/8" OD 32# T&C set at approximately 250' w/ 175 Sx.
Production String Casing to be 5 1/2" OD 15.5# to be set on top of or through the
producing zone - cement string w/ approx. 110 Sx.
Coring & Testing: Conventionally core the "D" sand if it runs structurally high.
Conventional Core: 10' into the "J" sand. DST all significant gas & oil shows.
Logging: (1) Run Schlumberger Electric Log from under surface casing to total depth.
Samples: 10' intervals from 4200-5050'.
5' intervals from 5050' to TD.
Depth Measurement: SIM of Drill Pipe at approx. 4000' & prior to coring DST and at TD.
Completion: To be determined by DST and geological evaluation.

Approved: John E. Brown
Dec 18 1950
State Oil Inspector

Company The British-American Oil Prod. Co.
Address P.O. Box 620, Casper, Wyo.
By C. Wm. Evelyn, Jr.
Title District Supt.

Submit reports of proposed work, for approval, on this form in Duplicate.