

File
117-1

COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



(Indicate nature of data by checking below)

Notice of intention to drill _____
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well _____
 Report of work done on well since previous report _____
 Subsequent Report of Squeeze and perforate. _____

March 23 19 53

Following is a (~~notice of intention to do work~~) (patented) described as follows:
 (report of work done)

Colorado	Logan	Yenter
State	County	Field
2	34	54W
(Well No.)	(Sec. and $\frac{1}{4}$ Sec.)	(Range) (Meridian)
Koenig-Ashby	SW/4	9N
(Lease)		(Twp.)

The well is located 330 ft. (N) of S. line and 990 ft. (E) of E. line
 (S) (W)

The elevation above sea level is 4363 ft. G.L.

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

November 19, 1952. Rigged up calbe tools and pulled rods, tubing and pump.
 November 20, 1952. Cleaned out to bottom and squeezed formation with 75 sax cement.
 November 24, 1952. Drilled out cement to 5229'. Old T.D. was 5234'. Perforated 5228'-5229'.
 No fillup. Drilled cement to 5233'. Perforated 5229'-5233'. Squeezed
 off perforations and drilled out cement to 5231' and perforated 5229½'
 to 5231' with 4 shots per foot.
 December 29, 1952. Placed well on production. Production prior to workover was a daily
 average of 47 BO and 151 BW. Production after workover was a daily
 average of 20 BO and 69 BW.

Approved: MAR 24 1953

J. J. Zischak
Director

Company THE BRITISH-AMERICAN OIL PRODUCING CO.

Address 831 - 14th St., Denver 2, Colorado

By *Thomas M. Hogan*

Title District Superintendent

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.