



OFFICE OF STATE OIL INSPECTOR
SUNDRY NOTICES AND REPORTS OF WELLS
LOCATED ON PRIVATE LANDS

Approved Copies
returned

138 D

(Indicate nature of data by checking below)

Notice of intention to drill.....
Notice of intention to change plans.....
Notice of date for test of water shut-off.....
Report on result of test of water shut-off.....
Notice of intention to re-drill or repair well.....
Notice of intention to clean out well.....
Statement of shooting.....
Statement of perforating and completing.....
Notice to pull or otherwise alter casing.....
Notice of intention to abandon well.....
Report of work done on well since previous report.....

Following is a (notice of intention to do work) (On land) 19.....
(report of work done) (patented) described as follows:

COLORADO	LOGAN	MT. HOPE
State	County	Field
B-1	C. F. GREEN	25 SE 9N 54W 6 P.M.
(Well No.)	(Lease)	(Sec. and $\frac{1}{4}$ Sec.) (Twp.) (Range) (Meridian)
The well is located 2372 ft. (N) of S Line and 330 ft. (X) of E Line (W)		

The elevation above sea level is 4182 ground ft. 4192 KB

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

After drilling firm cement from 4829 to 4896 with 7" casing cemented at 4901, perforations were placed in the casing opposite the oil bearing sand from 4875 to 4888 with 15/32 bullets. Tubing was landed at 4869.80, and swabbing began through tubing. After 112 $\frac{1}{2}$ barrels of oil was swabbed from hole, the well began to flow. From 10:00 P.M. 6-12-51 to 1:00 A.M. 6-13-51 well flowed 45 $\frac{1}{2}$ barrels of oil. The open flow for I.P. was calculated at 364 bbls. per day.

Approved: Sept 12 1951

State Oil Inspector

Company THE TEXAS CO.

Address BOX 1346, CASPER, WYO.

By Walter R. Ruhl

Title Dist. Superintendent

Submit reports of proposed work, for approval, on this form in Duplicate.