

OIL AND GAS CONSERVATION COMMISSION  
DEPARTMENT OF NATURAL RESOURCES  
OF THE STATE OF COLORADO

RECEIVED  
AUG 10 1979

RECEIVED  
AUG 30 1979



00245339

File in duplicate for Patented and Federal lands.  
File in triplicate for State lands.

COLORADO OIL & GAS CONSERVATION COMMISSION

COLORADO OIL & GAS CONSERVATION COMMISSION

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT" for such proposals.)

1. OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
2. NAME OF OPERATOR <u>Petroleum, Inc.</u>		7. UNIT AGREEMENT NAME	
3. ADDRESS OF OPERATOR <u>P.O. Box 60, Casper, WY 82601</u>		8. FARM OR LEASE NAME <u>Ramrod</u>	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface <u>700' FNL 1995' FEL C/ NW NE</u> At proposed prod. zone		9. WELL NO. <u>4-2</u>	
14. PERMIT NO.		10. FIELD AND POOL, OR WILDCAT <u>Ramrod</u>	
15. ELEVATIONS (Show whether DF, RT, GR, etc.) <u>4549 KB</u>		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA <u>Sec. 33-12N-55W</u>	
		12. COUNTY <u>Logan</u>	13. STATE <u>Colorado</u>

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>	WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>	FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON <input type="checkbox"/>	SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT <input checked="" type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>	(Other) _____	

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Date of work 7/11/79

Perforations in "J" Sand from 5800' to 5821' in depth. Ran sand over perms to 5795'. 5 sks. cement to 5751'. Casing record: 8-5/8" OD 20# 132' setting depth not recovered, 132' left in well. 5 1/2" OD 14.0# 30.48' to 4736.25' setting depth, 3699.28' recovered, 1006.49' left in well. 5 1/2" OD 15.5# 0' to 30.48' setting depth, 30.48' recovered, 0' left in well. 5 1/2" OD 15.5# 4736.25' to 5886' setting depth, 0' recovered, 1149.75' left in well. Method of parting - shot. Hole filled with mud laden fluid. Additional Plugs: ran 15 sks. cement 1/2 in 1/2 out of surface casing. Ran 5 sks. cement at surface with a welded steel plate on the stub; cut off 3' below surface.

DVR	<input checked="" type="checkbox"/>
POP	<input checked="" type="checkbox"/>
NHM	<input type="checkbox"/>
JAM	<input checked="" type="checkbox"/>
JJD	<input checked="" type="checkbox"/>
RLS	<input type="checkbox"/>
CGM	<input type="checkbox"/>

18. I hereby certify that the foregoing is true and correct  
SIGNED [Signature] TITLE District Production Supt. DATE Aug. 8, 1979

(This space for Federal or State office use)  
APPROVED BY [Signature] TITLE DIRECTOR DATE AUG 31 1979  
CONDITIONS OF APPROVAL, IF ANY:

X