

OIL AND GAS CONSERVATION COMMISSION DEPARTMENT OF NATURAL RESOURCES OF THE STATE OF COLORADO

File in duplicate for Patented and Federal lands.
File in triplicate for State lands.

RECEIVED

APR 20 1979

COLO. OIL & GAS CONS. COM.

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input checked="" type="checkbox"/> Water Injection Well		5. LEASE DESIGNATION AND SERIAL NO. C-0102279	
2. NAME OF OPERATOR Petroleum, Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
3. ADDRESS OF OPERATOR P.O. Box 60, Casper, Wyoming 82602		7. UNIT AGREEMENT NAME	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface SW SE Sect. 28-12N-55W At proposed prod. zone 610' FSL 660' FWL		8. FARM OR LEASE NAME Ramrod "J" Sand Unit	
14. PERMIT NO. 69-60		9. WELL NO. #1-1	
15. ELEVATIONS (Show whether DF, RT, GR, etc.) 4589 GL 4596 KB		10. FIELD AND POOL, OR WILDCAT Ramrod	
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sect. 28-12N-55W	
		12. COUNTY Logan	13. STATE Colorado

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐FRACTURE TREAT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐(Other) ☐PULL OR ALTER CASING ☐MULTIPLE COMPLETE ☐ABANDON ☒CHANGE PLANS ☐

SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐FRACTURE TREATMENT ☐SHOOTING OR ACIDIZING ☐(Other) ☐REPAIRING WELL ☐ALTERING CASING ☐ABANDONMENT ☐

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Date of work _____

All WI owners have now approved the abandonment of the above captioned secondary recovery unit. This is the only Federal Well involved. It is economically infeasible to operate. Work will be done as soon as possible, weather permitting. No other sands productive.

Plugging Instruction:

- 1.) Run sand over perforations plus 8 sks cement = 107.53 ft. on top of sand.
- 2.) Fill with 10# mud to 5350'.
- 3.) Set 11 sks cement plug from 5350 - 5200.
- 4.) Find free point and cut pipe.
- 5.) Fill to 4900' W/10# mud and pump 60 sks cement from 4900' to 4700'.
- 6.) Fill to 188' W/10# mud and run 15 sks of cement 1/2 in 1/2 out of surface casing to 144'.
- 7.) Run 5 sks. plug at surface W/a welded steel plate on the stub; cut off 3' below the surface.

This well is not ready for final inspection but will be rehabilitated as soon as possible.



00290904

18. I hereby certify that the foregoing is true and correct

SIGNED

TITLE Rocky Mountain Dist. Supt. DATE 4/18/79

(This space for Federal or State office use)

APPROVED BY

TITLE

DIRECTOR

U S G OIL & GAS

DATE APR 20 1979

CONDITIONS OF APPROVAL, IF ANY:

DVE	
FJP	
HMM	
JAM	
JJD	
RLS	
CRM	