

COLORADO OIL AND GAS CONSERVATION COMMISSION SUNDRY NOTICES AND REPORTS OF WELLS

RECEIVED
MAY 27 1955

(Indicate nature of data by check)



Notice of intention to drill (attach plat) _____
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well XXX _____
 Report of work done on well since previous report _____

Locate Well Correctly

	x		
		32	

12-N

Notice to do work ☒
 Report of work done ☐

Land: Fee and Patented ☒
 State ☐

54-W
 Lease No. _____

Colorado
 State

Logan
 County

Cliff
 Field

3 L. Hiscock NW/4 32 12-N 54-W 6th PM
 (Well No.) (Lease) (1/4 Sec.) (Sec.) (Twp.) (Range) (Meridian)

The Well is located 1980 Ft. (N) of Section Line and 1980 Ft. (E) of
 Section Line. (S) (W)

The elevation above sea level is _____ Ft. ALL MEASUREMENTS ARE SURFACE MEASUREMENTS

Details of Plan of Work: (State names of and expected depths to objective sands.
 Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing
 points, and all other important proposed work.)

- 5-16-55 Commenced drilling with rotary tools at 3:30 P.M.
 Having drilled to 94', ran and cemented 8-5/8" OD Casing at 92' with 100 sacks.
 5-22-55 Cored "D" sand, 5532-82, rec. 50 ft. - 1-1/2 ft. shale, 6 ft. reworked sand & shale
 3 ft. interbedded sand & shale, 22 ft. sand with streaks shale, fair stain, 3 ft.
 sand & shale, 8 ft. sand slight stain, odor and fluorescence and 6-1/2 ft. black
 shale.
 5-23-55 DST 5549-61, "D" Sand, 5/8" bottom choke, open 1 hour, rec. 480 ft. slightly oil
 cut water and 30 ft. slightly oil cut mud - FPO-190-SIP-15"-1030.
 5-24-55 Cored "J" Sand, 5646-52, rec. 6 ft. reworked sand and shale. Cored 5652-5700, "J"
 sand, rec. 48 ft. - 9 ft. sand and shale, 8 ft. black shale, 17 ft. brown sand, foul
 odor and fluorescence and 3 ft. white sand.
 5-25-55 Drilling to a depth of 5700-TD ran electric log and microlog.

Having drilled to 5700-TD, having cored the "D" and "J" sands, having run electric logs
 and microlog and having found no oil or gas in any zone, per verbal arrangements
 our Mr. T. C. Kadel with your Mr. Frank J. Kirchman, we propose to plug and abandon
 as follows: Spot 25 sacks cement 5562-5500 and spot 20 sacks cement 150-125; cut
 off 8-5/8" OD Casing 3' below ground level and dump 5 sacks cement in top of casing
 & weld steel plate on top. We will back fill the pits with earth & clean the well site.

Approved: MAY 27 1955

Date May 26, 1955

Company Sinclair Oil & Gas Company
 601 Denver Club Building
 Address Denver, Colorado

By JA Jackman
 Title Division Superintendent

Submit reports of proposed work, for approval, on this form in Duplicate for patented
 lands and in Triplicate for school and state lands.