

FORM  
5Rev  
12/20

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

403193182

Date Received:

## DRILLING COMPLETION REPORT

Per Rule 308A, this form and all required attachments shall be submitted after completing the drilling operations to drill, sidetrack, or deepen a wellbore and after changing the casing and/or cement configuration of a wellbore. If any attempt has been made to test, complete, or produce the well, the operator shall also submit a Form 5A (Completed Interval Report) per Rule 308B. If the well has been plugged, the operator shall also submit a Form 6 (Well Abandonment Report) per Rule 311.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 96850

Contact Name: Jeff Kirtland

Name of Operator: TEP ROCKY MOUNTAIN LLC

Phone: (970) 263-2736

Address: 1058 COUNTY ROAD 215

Fax:

City: PARACHUTE

State: CO

Zip: 81635

Email: jkirtland@terraep.com

API Number 05-045-24478-00

County: GARFIELD

Well Name: FEDERAL

Well Number: NR 444-36

Location: QtrQtr: NWSW Section: 3 Township: 6S Range: 94W Meridian: 6  
FNL/FSL FEL/FWL

Footage at surface: Distance: 2448 feet Direction: FSL Distance: 1250 feet Direction: FWL

As Drilled Latitude: 39.554251 As Drilled Longitude: -107.879110

GPS Data: GPS Quality Value: 3.1 Type of GPS Quality Value: PDOP Date of Measurement: 06/10/2021

\*\* If directional footage at Top of Prod. Zone Dist: 384 feet Direction: FSL Dist: 622 feet Direction: FEL  
Sec: 36 Twp: 5S Rng: 94W  
FNL/FSL FEL/FWL

\*\* If directional footage at Bottom Hole Dist: 454 feet Direction: FSL Dist: 672 feet Direction: FEL  
Sec: 36 Twp: 5S Rng: 94W  
FNL/FSL FEL/FWL

Field Name: RULISON

Field Number: 75400

Federal, Indian or State Lease Number: COC73085

Spud Date: (when the 1st bit hit the dirt) 07/15/2022 Date TD: 07/21/2022 Date Casing Set or D&amp;A: 07/21/2022

Rig Release Date: 08/23/2022 Per Rule 308A.b.

Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 11313 TVD\*\* 10064 Plug Back Total Depth MD 11266 TVD\*\* 10017

Elevations GR 6728 KB 6758 Digital Copies of ALL Logs must be Attached ☒

List All Logs Run:

CBL, (Triple Combo on 045-20525)

## FLUID VOLUMES USED IN DRILLING OPERATIONS

(Enter "0" if a type of a fluid was not used. Do not leave blank.)

Total Fluids (bbls): 6599 Fresh Water (bbls): 5826

Recycled or Reused Fluids That Offset the Use of Fresh Water (bbls): 773

**CASING, LINER AND CEMENT**

Casing Type	Size of Hole	Size of Casing	Grade	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top	Status
CONDUCTOR	30	20	X65	78.67	0	82	194	82	0	VISU
SURF	13+1/2	9+5/8	J-55	36	0	1133	362	1133	0	VISU
1ST	8+3/4	4+1/2	P-110	11.6	0	11303	1220	11313	4605	CBL

Bradenhead Pressure Action Threshold 340 psig

This threshold is calculated per Rule 308A.b.(2)G. If this well is located in a bradenhead test area (see Rule 207.b) per an Order of the Commission, it may be subject to a different threshold.

Does the casing centralization comply with Rule 317.g? Yes

If "NO", provide details below.

**STAGE/TOP OUT/REMEDIAL CEMENT**

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

**FORMATION LOG INTERVALS AND TEST ZONES**

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH	0				
WASATCH G	4,327				
OHIO CREEK	7,451				
WILLIAMS FORK	8,176				
CAMEO	10,451				
ROLLINS	11,238				

Operator Comments:

The GPS "as drilled" coordinates and date of measurement is actual data of the existing well conductor location prior to the spud date.

No Open Hole Logs were run on this well. Triple Combo log ran on the Clough NR 422-3 (045-20525).

No MUD logs were run on this well.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Ashley Noonan

Title: Sr. Regulatory Analyst

Date: \_\_\_\_\_

Email: anoonan@terraep.com

### Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
403204975	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
403201065	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
403201040	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
403201049	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
403201068	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)