

Well Name **GM 230-34**
 Location **NWSW 34-T6S-R96W**
 Field **Grand Valley**
 County **Garfield**
 API **05-045-07688**
 Elevation_KB **5,378' (14')**
 Elevation_GL **5,364'**
 Footages **1499 FSL 1115 FWL**

Spud 5/24/2001

Conductor

Surf Casing	0'-303'	9-5/8"	32#
Cement 180 sks 14.5 lb/gal 1.34 cuft/sk			
Prod Casing	0'-6,319'	4-1/2"	11.6#
Cement 350 sks 12.5 lb/gal 1.75 cuft/sk 450 sks 14.2 lb/gal 1.33 cuft/sk			
Tubing	Landed at 5,798'	2-3/8"	

9-5/8", 0'-303'
Hole size: 13-1/2"

Formation Tops:

Lower Wasatch	3,088'
Ohio Creek	3,375'
Mesaverde	3,380'
Cameo Coal	5,850'
Rollins	6,340'

L Wasatch - 3,088'

Ohio Creek - 3,375'

Mesaverde - 3,380'

TOC @ 3,900'

TOC -

Production Intervals

	<u>Top Perf</u>	<u>Bottom Perf</u>
Mesaverde/Cameo	4,632'	6,231'

EOT @ 5,798'

Cameo Coal - 5,850'

Rollins - 6,340'

4-1/2", 0'-6,319'
Hole size: 7-7/8"

Prepared By: Christian Carroll
Office phone: 832-982-5167

Revision Date:
10/26/2022