

Well Name TW 1-32
Location NWSW 32-T6S-R96W
Field Parachute
County Garfield
API 05-045-06537
Elevation_KB 5,710' (14')
Elevation_GL 5696'
Footages 1750 FNL 1900 FWL

Spud 07/07/1987

Conductor

Surf Casing	0'-304'	8-5/8"	22.6#
Cement 175 sks			
Prod Casing	0-2,499'	4-1/2"	10.5#
Cement 325 sks			
Tubing	Landed at 1,920'	2-3/8"	

8-5/8", 0'-304'
Hole size: 12-1/4"

Formation Tops:

Wasatch G 1950'
Fort Union 2305'

TOC @ 1,600'

TOC - 1,600-ft

Production Intervals

Top Perf

Bottom Perf

Wasatch G/Fort Union

1,952'

2,034'

EOT @ 1,920'

Wasatch G - 1,950'

Fort Union - 2,305'

4-1/2", 0'-2,499'
Hole size: 6- 3/4"

Prepared By: Christian Carroll
Office phone: 832-982-5167

Revision Date:
10/26/2022