

Schenk 1

Pumping

Today - 11/2/2022

API #	Lease ID	Permit #	County	KB	GL	Current production			Sec N/S	Sec E/W	Sec
05-017-07421		94-419	Cheyenne	4375'	4366'	2.0 BOPD	0 MCFD	38 BWPD	1980' S	600' W	5-13S-44W
Pumping Unit		Motor	State	TD	PBTD	Initial production			Lease N/S	Lease E/W	Blk
KB = 9'		LUF M228-200-86	CO	5621'		74 BOPD	TSTM	18 BWPD			

Perforations

Top	Bottom	SPF	Stimulation	OPEN?
5489'	5500'	1995	250 Gal 15%	YES
5516'	5528'	1994	500 gal 15% MCA	YES
5561'	5562'		250 Gal 15%	YES
5568'	5574'		250 Gal 15%	YES

Total = 30'

Casing

Depth	Size	Wgt (#)	Grade	Description
422'	8-5/8"	24		
5620'	5-1/2"	15.5		DV tool

Cement

Casing	Sacks	TOC	Description
8-5/8"	250	surface	150 sx lite; 100sx H
5-1/2"	240	1750, 5000	lower: 100 sx H; upper: 90sx lite,

Tubing

Description	Size	Length	Top	Bot
174 jts tbg	2-7/8"	5430'	0'	5430'
TAC		3'	5430'	5433'
5 jts tbg	2-7/8"	155'	5433'	5588'
SN		1'	5588'	5589'
MA		15'	5589'	5604'

Rods

Description	Size	Length	Top	Bot
Polished Rod	1-1/4"	22'	-3'	19'
3 Pony Rods	7/8"	18'	19'	37'
97 Rods	7/8"	2425'	37'	2462'
110 Rods	3/4"	2750'	2462'	5212'
15 Rods	7/8"	375'	5212'	5587'
Pump	1-3/4"	16'	5587'	5603'

Pump

2-1/2" X 1-3/4" X 16' RHBC

