

OPERATOR: K.P. Kauffman Company Inc.

WELL: HARRIET W LUCKE #2

FIELD: SPINDLE

API # 05-123-08797

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 6/18/1976

COMP: 7/29/1976

STATUS: SI

WBD DATE: 8/16/2022

FTG:

Q-Q: SWSW

SEC.: 28

TWS: 1N

RGE: 67W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 5010 '

KB: 8 '

GLE: 5002 '

TD (ft): 4990

PBTD (ft): 4925

12.25" Hole
8.625" 24# Csg @839 '
Cmtd w/600 sxs

TOC @ 3973 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @4983 '
Cmtd w/200 sxs

SUSSEX Perfs
4828'-4856'

PBTD (ft): 4925 '

TD (ft): 4990 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>839</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>4983</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4828</u>	<u>4856</u>	<u>58</u>		