

OPERATOR: K.P. Kauffman Company Inc.

WELL: KIYOTA #2

FIELD: SPINDLE

API # 05-123-09388

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 1/9/1978

COMP: 2/8/1978

STATUS: SI

WBD DATE: 8/16/2022

FTG:

Q-Q: NWSE

SEC.: 36

TWS: 2N

RGE: 67W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 4899 '

KB: 10 '

GLE: 4889 '

TD (ft): 4781

PBTD (ft): 4779

12.25" Hole
8.625" 23# Csg @769 '
Cmtd w/600 sxs

TOC @ 3766 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @4776 '
Cmtd w/200 sxs

SUSSEX Perfs
4644'-4670'

PBTD (ft): 4779 '

TD (ft): 4781 '

CASING RECORD

| HOLE (in) | SIZE (in) | WT (lb/ft) | GRADE | TOP (ft) | BTM (ft) |
|---------------|--------------|-------------|-------|----------|-------------|
| <u>12 1/4</u> | <u>8 5/8</u> | <u>23</u> | | <u>0</u> | <u>769</u> |
| <u>7 7/8</u> | <u>4 1/2</u> | <u>10.5</u> | | <u>0</u> | <u>4776</u> |

TUBING RECORD

| SIZE (in) | WT (lb/ft) | GRADE | JOINTS | BTM (ft) |
|-----------|------------|-------|--------|----------|
| | | | | |

PERFORATION RECORD

| ZONE | TOP (ft) | BTM (ft) | HOLES | STAGE | STATUS |
|---------------|-------------|-------------|-----------|-------|--------|
| <u>SUSSEX</u> | <u>4644</u> | <u>4670</u> | <u>27</u> | | |