

OPERATOR: K.P. Kauffman Company Inc.
WELL: MARTIN T. HART #2
FIELD: SPINDLE
API # 05-123-09127
LEASE #: _____
UIC #: _____

CNTY: WELD
STATE: CO
SPUD: 1/23/1977
COMP: 3/24/1977
STATUS: PR
WBD DATE: 8/17/2022

FTG: _____
Q-Q: SESW
SEC.: 27
TWS: 2N
RGE: 67W
BY: _____

CURRENT WELLBORE DIAGRAM

KBE: 5012 '
KB: 10 '
GLE: 5002 '

TD (ft): 4830
PBDT (ft): 4798

12.25" Hole
8.625" 24# Csg @735 '
Cmtd w/550 sxs

TOC @ 3558 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @4820 '
Cmtd w/250 sxs

SUSSEX Perfs
4664'-4702'

PBDT (ft): 4798 '
TD (ft): 4830 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>735</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>4820</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4664</u>	<u>4702</u>	<u>78</u>		