

OPERATOR: K.P. Kauffman Company Inc.

WELL: SUCKLA D UNIT #2

FIELD: SPINDLE

API # 05-123-08845

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 7/27/1976

COMP: 12/22/1976

STATUS: PR

WBD DATE: 8/18/2022

FTG:

Q-Q: SENW

SEC.: 33

TWS: 2N

RGE: 67W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 5086 '

KB: 4 '

GLE: 5082 '

TD (ft): 4866

PBTD (ft): 4826

12.25" Hole
8.625" 24# Csg @804 '
Cmtd w/600 sxs

TOC @ 3857 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @4867 '
Cmtd w/200 sxs

SUSSEX Perfs
4704'-4762'

PBTD (ft): 4826 '

TD (ft): 4866 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
12 1/4	8 5/8	24		0	804
7 7/8	4 1/2	10.5		0	4867

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
SUSSEX	4704	4762	118		