

OPERATOR: **K.P. Kauffman Company Inc.**

WELL: **MORIE GERHARDT B #6**

FIELD: **SPINDLE**

API # **05-123-08914**

LEASE #:

UIC #:

CNTY: **WELD**

STATE: **CO**

SPUD: **9/5/1976**

COMP: **11/19/1976**

STATUS: **SI**

WBD DATE: **8/25/2022**

FTG:

Q-Q: **SENE**

SEC.: **23**

TWS: **2N**

RGE: **67W**

BY:

CURRENT WELLBORE DIAGRAM

KBE: **4926** '

KB: **8** '

GLE: **4918** '

TD (ft): **4770**

PBTD (ft): **4738**

12.25" Hole
8.625" 24# Csg @ **675** '
Cmtd w/475 sxs

TOC @ **3760** '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @ **4770** '
Cmtd w/200 sxs

SUSSEX Perfs
4550'-4590'

PBTD (ft): **4738** '

TD (ft): **4770** '

CASING RECORD

| HOLE (in) | SIZE (in) | WT (lb/ft) | GRADE | TOP (ft) | BTM (ft) |
|---------------|--------------|-------------|-------|----------|-------------|
| 12 1/4 | 8 5/8 | 24 | | 0 | 675 |
| 7 7/8 | 4 1/2 | 10.5 | | 0 | 4770 |

TUBING RECORD

| SIZE (in) | WT (lb/ft) | GRADE | JOINTS | BTM (ft) |
|-----------|------------|-------|--------|----------|
| | | | | |

PERFORATION RECORD

| ZONE | TOP (ft) | BTM (ft) | HOLES | STAGE | STATUS |
|---------------|-------------|-------------|-----------|-------|--------|
| SUSSEX | 4550 | 4590 | 82 | | |