

OPERATOR: K.P. Kauffman Company Inc.

WELL: UPRR 43 PAN AM I #5

FIELD: SPINDLE

API # 05-123-08674

LEASE #:

UIC #:

CNTY: DACONO/WELD

STATE: CO

SPUD: 4/20/1976

COMP: 5/27/1976

STATUS: SI

WBD DATE: 9/1/2022

FTG:

Q-Q: NENW

SEC.: #

TWS: 1N

RGE: 68W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 5115 '

KB: 7 '

GLE: 5108 '

TD (ft): 4956 '

PBTD (ft): 4922 '

12.25" Hole
8.625" 24# Csg @ 765 '
Cmtd w/200 sxs

TOC @ 3653 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 11.6# Csg @ 4915 '
Cmtd w/250 sxs

SUSSEX Perfs
4837'-4855'

PBTD (ft): 4922 '

TD (ft): 4956 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>765</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>11.6</u>		<u>0</u>	<u>4915</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4837</u>	<u>4855</u>	<u>38</u>		