

OPERATOR: K.P. Kauffman Company Inc.

WELL: 1415 CORP GAS UNIT B #1

FIELD: SPINDLE

API # 05-123-07781

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 7/27/1973

COMP: 8/1/1973

STATUS: PR

WBD DATE: 9/7/2022

FTG:

Q-Q: SWSW

SEC.: 14

TWS: 2N

RGE: 67W

BY:

## CURRENT WELLBORE DIAGRAM

KBE: 4977 '

KB: 10 '

GLE: 4967 '

TD (ft): 4775

PBTD (ft): 4703

12.25" Hole  
8.625" 24# Csg @ 586 '  
Cmtd w/550 sxs

TOC @ 2241 '  
Calc Assuming 1.15 yield

7.875" Hole  
4.5" 10.5# Csg @ 4765 '  
Cmtd w/500 sxs

SUSSEX Perfs  
4628'-4670'

PBTD (ft): 4703 '

TD (ft): 4775 '

### CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>586</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>4765</u>

### TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

### PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4628</u>	<u>4670</u>	<u>60</u>		