

OPERATOR: K.P. Kauffman Company Inc.

WELL: CARL DEEPE C #4

FIELD: SPINDLE

API # 05-123-09201

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 4/19/1977

COMP: 7/1/1977

STATUS: SI

WBD DATE: 9/7/2022

FTG:

Q-Q: NWSW

SEC.: 22

TWS: 2N

RGE: 67W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 5029 '

KB: 10 '

GLE: 5019 '

TD (ft): 5209 '

PBTD (ft): 5167 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>702</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>5199</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4654</u>	<u>4690</u>	<u>74</u>		
<u>SHANNON</u>	<u>5084</u>	<u>5092</u>	<u>18</u>		

12.25" Hole
8.625" 24# Csg @ 702 '
Cmtd w/500 sxs

TOC @ 2675 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @ 5199 '
Cmtd w/500 sxs

SUSSEX Perfs
4654'-4690'

SHANNON Perfs
5084'-5092'

PBTD (ft): 5167 '

TD (ft): 5209 '