

OPERATOR: K.P. Kauffman Company Inc.

WELL: DITLEV-SIMONSEN C #2

FIELD: SPINDLE

API # 05-123-08988

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 10/7/1976

COMP: 12/21/1976

STATUS: PR

WBD DATE: 9/8/2022

FTG:

Q-Q: NWSW

SEC: 31

TWS: 2N

RGE: 67W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 5000 '

KB: 10 '

GLE: 4990 '

TD (ft): 5207 '

PBTD (ft): 5142 '

DV TOOL @ 171 '

Cmtd w/ 250 sxs

12.25" Hole

8.625" 24# Csg @ 600 '

Cmtd w/250 sxs

TOC @ 3420 '

Calc Assuming 1.15 yield

7.875" Hole

4.5" 10.5# Csg @ 5187 '

Cmtd w/350 sxs

SUSSEX Perfs

4660'-4686'

SHANNON Perfs

5084'-5106'

PBTD (ft): 5142 '

TD (ft): 5207 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>600</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>5187</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4660</u>	<u>4686</u>	<u>54</u>		
<u>SHANNON</u>	<u>5084</u>	<u>5106</u>	<u>46</u>		