

OPERATOR: K.P. Kauffman Company Inc.

WELL: ELKHORN COMPANY B #5

FIELD: SPINDLE

API # 05-123-08694

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 5/5/1976

COMP: 8/19/1976

STATUS: PR

WBD DATE: 9/8/2022

FTG:

Q-Q: SWNE

SEC.: 21

TWS: 2N

RGE: 67W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 5045 '

KB: 10 '

GLE: 5035 '

TD (ft): 5210 '

PBTD (ft): 5172 '

12.25" Hole
8.625" 24# Csg @ 621 '
Cmtd w/550 sxs

TOC @ 3702 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @ 5217 '
Cmtd w/300 sxs

SUSSEX Perfs
4644'-4696'

SHANNON Perfs
5083'-5111'

PBTD (ft): 5172 '

TD (ft): 5210 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>621</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>5217</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4644</u>	<u>4696</u>	<u>106</u>		
<u>SHANNON</u>	<u>5083</u>	<u>5111</u>	<u>58</u>		