

OPERATOR: K.P. Kauffman Company Inc.

WELL: HAUDRICH #1

FIELD: SPINDLE

API # 05-123-07893

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 12/9/1973

COMP: 1/18/1974

STATUS: PR

WBD DATE: 9/8/2022

FTG:

Q-Q: NWNW

SEC.: 21

TWS: 2N

RGE: 66W

BY:

## CURRENT WELLBORE DIAGRAM

KBE: 4952 '

KB: 6 '

GLE: 4946 '

TD (ft): 4800

PBTD (ft): 4742

12.25" Hole  
8.625" 23# Csg @ 580 '  
Cmtd w/350 sxs

TOC @ 3072 '  
CBL

7.875" Hole  
5.5" 15/14# Csg @ 4800 '  
Cmtd w/240 sxs

SUSSEX Perfs  
4659'-4694'

PBTD (ft): 4742 '

TD (ft): 4800 '

### CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>23</u>		<u>0</u>	<u>580</u>
<u>7 7/8</u>	<u>5 1/2</u>	<u>15/14</u>		<u>0</u>	<u>4800</u>

### TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

### PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4659</u>	<u>4694</u>	<u>27</u>		