

OPERATOR: K.P. Kauffman Company Inc.

WELL: HAZEL MCHALE #3

FIELD: SPINDLE

API # 05-123-08998

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 10/15/1976

COMP: 12/30/1976

STATUS: PR

WBD DATE: 9/8/2022

FTG:

Q-Q: NWSE

SEC.: 26

TWS: 2N

RGE: 67W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 4950 '

KB: 9 '

GLE: 4941 '

TD (ft): 4830

PBTD (ft): 4803

12.25" Hole
8.625" 24# Csg @ 747 '
Cmtd w/525 sxs

TOC @ 3813 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @ 4823 '
Cmtd w/200 sxs

SUSSEX Perfs
4690'-4722'

PBTD (ft): 4803 '

TD (ft): 4830 '

CASING RECORD

| HOLE (in) | SIZE (in) | WT (lb/ft) | GRADE | TOP (ft) | BTM (ft) |
|-----------|-----------|------------|-------|----------|----------|
| 12 1/4 | 8 5/8 | 24 | | 0 | 747 |
| 7 7/8 | 4 1/2 | 10.5 | | 0 | 4823 |

TUBING RECORD

| SIZE (in) | WT (lb/ft) | GRADE | JOINTS | BTM (ft) |
|-----------|------------|-------|--------|----------|
| | | | | |

PERFORATION RECORD

| ZONE | TOP (ft) | BTM (ft) | HOLES | STAGE | STATUS |
|--------|----------|----------|-------|-------|--------|
| SUSSEX | 4690 | 4722 | 66 | | |