



00230262

This summary geological report is for:

Edward Mike Davis #1-11 UPRR-Flader
SE $\frac{1}{4}$ SW $\frac{1}{4}$ Section 11, T3S-R59W
Adams County, Colorado

Spud Date: October 3, 1971

Surface Casing: Set 8-5/8" at 127' KBM. Cemented with 150 sacks cement.

Contractor: Tiger Drilling Company, Rig #3, Dick Phillips, Pusher

Hole Size: 7-7/8"

Cores: None

Drill Stem Tests: None

Logs: Schlumberger IES and FDC-Gamma Ray with calipers.

Log Date: October 9, 1971

Disposition: Plugged with 15 sacks base of surface casing and 10 sacks
top of surface casing. Plugging directions from Mr.
James McKee of Colorado Oil and Gas Commission.

Log Tops:

Elevation 5106 Gr. 5115 KB

Niobrara	5296
Fort Hays	5699
Carlile	5742
Greenhorn	5806
Bentonite	6040
"D" Sand	6134 (-1019)
"J" Sand	6188 (-1073)
Total Depth	6305 Log: 6304 Driller