



00230250

December 18, 1981

JUL 31 1985

COLO. OIL & GAS CONS. COMM.

DAILY DRILL REPORT
DRILLING

LADD & LUKOWICZ OPERATED

UPRR Linnebur #1-9
Adams Co., Colorado
Proposed TD: 6309'
Denton Bros. Rig #3NE Cabin Creek Prospect
CADJ Package II
(WI 12.5%)LATE ADDITION TO 12-17-81 REPORT

Smple Top "D" Sand @ 6074'. Present depth @ 6120' still in "D" Sand. Smple description: ss, f gr, lt gy, lt oil stn, good gold fluor, fair to good p&p, w/fair cut. Will DST from 6076' to 6120'.

12-18-81 - Depth 6121' (21' in 3 hrs). TIH w/bit #5. Day 7. MW 9.3, VIS 58, WL 6.4, PH 9.5. DST #1 from 6077'-6121'. Rec'd 240' mud, tr oil, hly gas cut; 300' muddy wtr, hly gas cut; 1841' clear wtr, hly gas cut. Smplr 1300 cc wtr, tr oil, 25#, Rw .8 @ 68°. IHP 3118, IF 489-760, ISIP 1489, FF 869-1054, FSIP 1489, FHP 3100.

DAILY - \$ 9,050
CUM - \$90,802DRY HOLE - \$ 85,000
AFE AMT. - \$380,000-----
COMPLETING

LADD & LUKOWICZ OPERATED

ICLO #1-33
Texas Co., Oklahoma
PBTD: 2430'DeFault Prospect
JV '81
(WI 75%)

12-18-81 - SICP 20#. Swbd 146 BF in 9 hrs. FL remained at 1600' while swabbing. Very little gas.

DAILY - \$ 1,850
CUM - \$285,370

AFE AMT. - \$393,100

COMPLETING

LADD & LUKOWICZ OPERATED

Fred Dilts #1
Campbell Co., Wyoming
PBTD: 9177'NW Fenton Prospect
JV '80
(WI 40%)

12-16-81 - Flwd 210 BO, 625 MCF in 18 hrs. Flowing press. 300# 22/64" choke.

5