

OPERATOR: K.P. Kauffman Company Inc.

WELL: PETE MONTOYA #2

FIELD: SPINDLE

API # 05-123-08963

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 10/7/1976

COMP: 12/21/1976

STATUS: PR

WBD DATE: 9/9/2022

FTG:

Q-Q: SENW

SEC.: 35

TWS: 2N

RGE: 67W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 4960 '

KB: 9 '

GLE: 4951 '

TD (ft): 4840

PBTD (ft): 4804

12.25" Hole
8.625" 24# Csg @ 655 '
Cmtd w/475 sxs

TOC @ 3830 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @ 4840 '
Cmtd w/200 sxs

SUSSEX Perfs
4636'-4696'

PBTD (ft): 4804 '

TD (ft): 4840 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
12 1/4	8 5/8	24		0	655
7 7/8	4 1/2	10.5		0	4840

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
SUSSEX	4636	4696	122		